

WATER INFRASTRUCTURE

CONFIRMATION BY A CHARTERED ENGINEER AND TEST RESULT CERTIFICATES & REPORTS INDICATING THAT THE WATER INFRASTRUCTURE HAS UNDERGONE APPROPRIATE ON-SITE TESTING, OFF SITE TESTING AND COMMISSIONING. THE APPROPRIATE SITE TESTS FOE WATER COLLECTION INFRASTRUCTURE WOULD BE AS FOLLOWS:

 IGN TEST REPORTS – WATERMAIN PRESSURE TESTING SERVICE CONNECTION TEST RESULTS

ELECTRO/BUTT FUSION WELD TEST RESULT REPORTS (DESTRUCTIVE TESTING)

ALL PIPE MATERIALS TO COMPLY WITH SECTION 3.9 OF THE IRISH WATER CODE OF

PRINTOUT OF THE JOINT DETAILS, WITH A GPS LOCATION OF EACH ELECTROFUSION &

BUTT FUSION JOINT TESTING COMPLETION RESULTS FOR BOOSTER PUMP PLANT (IF APPROPRIATE)

 SWABBING & FLUSHNG RECORDS DISINFECTION TEST REPORTS (ACCREDITED LABORATORY REPORT)

WATER QUALITY SAMPLING RESULTS (ACCREDITED LABORATORY REPORT)

 ALL WORKS TO BE CARRIED OUT TO IRISH WATER CODE OF PRACTICE DOCUMENT CDS-5020-03

WASTE WATER INFRASTRUCTURE

PRACTICE

CONFIRMATION BY A CHARTERED ENGINEER AND TEST RESULT CERTIFICATES INDICATING THAT THE WASTEWATER INFRASTRUCTURE HAS UNDERGONE APPROPRIATE ON-SITE TESTING AND COMMISSIONING. THE APPROPRIATE SITE TESTS FOE WASTEWATER

COLLECTION INFRASTRUCTURE WOULD BE AS FOLLOWS: AIR TESTS AND WATER TESTS COMPLETION RESULTS FOR SEWERS

 WATER RETAINING TESTS COMPLETION RESULTS FOR MANHOLES AND PUMPING STATION STRUCTURES PRESSURE TESTING COMPLETION RESULTS OF RISING MAINS COMPLETE WITH A HARD

COPY PRINT OUT FROM THE LOGGER OF THE RELAXATION CURVE AS PROOF OF THE OUTCOME OF THE TEST. (IGN 4-01-03 COMPLIANT REPORT)

A PRINTOUT OF THE JOINT DETAILS, WITH A GPS LOCATION OF EACH JOINT (HDPE)

PUMPING STATIONS – TESTING & COMMISSIONING REPORTS

WASTEWATER INFRASTRUCTURE - CCTV & MANHOLE SURVEY REPORTS

REPORTING AND DELIVERING - THE FINAL REPORTS AND DELIVERABLES TO IRISH WATER SHALL INCLUDE THE FOLLOWING ITEMS:

A- CCTV SURVEY FOOTAGE: FILES IN "XML" FORMAT SUBMITTED TO IRISH IN ACCORDANCE WITH MSCC, 5TH ADDITION, COMPATIBLE WITH INFONET. B – CCTV REPORTS: REPORTS SUBMITTED IDENTIFYING THAT NO DEFECTS EXIST. REPORTS SUBMITTED IN CD OR DVD FORMAT WITH A HARD COPY OF THE SURVEY REPORT. C - MANHOLE SURVEY REPORTS: REPORTS SUBMITTED IDENTIFYING THAT NO DEFECTS EXIST. REPORTS SUBMITTED IN "CSC" FORMAT ON CD OR DVD WITH A HARD COPY OF THE SURVEY REPORTS. MANHOLE REFERENCING SHALL BE CONSISTENT WITH THE AS CONSTRUCTED DRAWINGS __ TO IRISH NATIONAL GRID COORDINATES (ING)) TO +/- 100mm

ACCURACY IN THE HORIZONTAL PLANE, WITH DIMENSIONS RELATING TO FIXED ORDNANCE SURVEY CO-ORDINATES. D - CERTIFICATION FROM THE CUSTOMERS CONSULTANT ENGINEER: CONFIRMATION THAT A QUALITY CONTROL REGIME HAS BEEN IMPLEMENTED WITH THE RESULT THAT NO DEFECTS EXIST IN EITHER THE SEWERS OR THE MANHOLES.

NOTES

INDIVIDUAL WASTEWATER CONNECTION TO EACH DWELLING WILL BE AS PER STANDARD DETAIL STD-WW-02.

REFER TO SECTION 3.2 FOR SERVICE CONNECTION GRADIENTS.

THE INSPECTION CHAMBER WILL BE IN COMPLIANCE WITH STD-WW-03 AND STD-WW-13 AND WILL BE LOCATED WITHIN 1M OF EACH SITE BOUNDARY.

PIPE MATERIALS SHALL COMPLY WITH SECTION 3.13. OF THE IRISH WATER CODE OF

PIPE MATERIALS WILL BE UNPLASTICISED PVC FOR THE MAIN SEWERS AS PER SECTION 3.13.3

OF THE IRISH WATER CODE OF PRACTICE.

MANHOLES WILL CONFORM TO STANDARD DETAILS STD-WW-09, STD-WW-10, STD-WW-11 AND/OR STD-WW-12 AS APPROPRIATE.

SEPARATION DISTANCES FROM FOUL SEWERS TO STRUCTURES AND OTHER UTILITIES WILL COMPLY WITH SECTION 3.5 OF THE IRISH WATER CODE OF PRACTICE.

REFER TO STD-W-12A, STD-WW-06, STD-WW-06A & 3.26 OF THE IRISH WATER CODE OF PRACTICE FOR PLANTING RESTRICTIONS OF WATER AND WASTE WATER. ROOT PROTECTION TO BE REROOT 2000 OR SIMILAR.

REFER TO DETAILSTD-W-11 FOR TYPICAL SERVICES LAYOUT DISTANCES & STD-WW-05 FOR WASTEWATER TYPICAL SERVICES LAYOUT AND 3.21 IRISH WATER WASTEWATER CODE OF

REFER TO SECTION 3.5.16 OF THE WASTE WATER IRISH WATER CODE OF PRACTICE FOR UNAVOIDABLE SERVICES CROSSOVER.

MANHOLE COVERS LOCATED IN GRASS AREAS TO HAVE 200mm ALL ROUND CONCRETE PLINTH AND 100mm DEEP FORMED C⅔ CONCRETE, 20mm AGGREGATE, BEDDED IN CLAUSE 804

REFER TO 3.5.13 OF THE IRISH WATER CODE OF PRACTICE FOR STAGGERED MANHOLE SYSTEMS DETAILS.

EXTERNAL FACE OF PROPOSED MANHOLE CHAMBER TO BE A MINIMUM OF 0.5m FROM KERB LINE AND EXTERNAL FACE OF SEWERS ARE A MINIMUM OF 1M FROM KERB LINE. SEE SECTION 3.5.15 OF IRISH WATER WASTEWATER CODE OF PRACTICE

ALL WORKS TO COMPLY WITH THE RECOMMENDATIONS FOR SITE DEVELOPMENT WORKS FOR HOUSING AREAS AS ISSUED BY THE DEPARTMENT OF THE ENVIRONMENT NOVEMBER 1998

ALSO REFER TO ALAN TRAYNOR CONSULTING ENGINEERS GENERAL SPECIFICATION

ALL SEWER PIPES WITH LESS THAN 1200MM COVER IN ROADS AND 600MM ELSEWHERE TO BE SURROUNDED IN MINIMUM 150MM THICK CONCRETE (35N/20)

THIS DRAWING TO BE READ IN CONJUNCTION WITH ARCHITECTS DRAWINGS **EXACT START & FINISHED LEVELS TO BE CONFIRMED ON SITE**

ALL MANHOLE COVERS TO BE LOADING CLASS D400 AND TO BE LOCKABLE

LOCATION AND LEVELS OF ALL EXISTING SERVICES TO BE CONFIRMED ON SITE AND RECORDED TO ALL NECESSARY PARTIES PRIOR TO ANY CONSTRUCTIONS

LEGEND			
PROPOSED WATERMAIN	100mm HDPE CLASS C WATERMAIN		
EXISTING WATERMAIN			
SLUICE VALVE	⊕ SV		
HYDRANT	Hyd		
AIR VALVE	⊕ AV		
BULK METER	M		
WATER BOUNDARY BOX	•		
FINISHED FLOOR LEVELS	FFL 63.700		
FINISHED ROAD LEVELS	+ 63.350		
SITE BOUNDARY			

_			
_			
REV.	DATE	DESCRIPTION	APPROVED

COPYRIGHT RESERVED- THIS DRAWING IS NOT TO BE USED FOR A PURPOSE OTHER THAN THAT FOR WHICH IT HAS BEEN ISSUED BY ALAN TRAYNOR CONSULTING NOR IS IT TO BE COPIED OR REPRODUCED IN ANY MATTER WITHOUT WRITTEN

Alan Traynor Consulting Engineers Ltd

Unit 6, Belturbet Business Park, Creeny, Belturbet, Co.Cavan H14AY94 TEL: (+353) 499522236 2nd Floor, 67–70 Meath St, Dublin 8 D08XY53



TEL: (+353) 19697881 Email: info@alantraynor.com Website: www.alantaynor.com

MEATH COUNTY COUNCIL

PITCHER LANE HOUSING DEVELOPMENT PITCHER LANE, KELLS, CO. MEATH

DRAWING TITLE

SITE SERVICES LAYOUT PROPOSED WATERMAIN

1	SCALE	DRAWN	CHECKED	APPROVED
	1:250	JOHN O'REILLY	LIAM MCELGUNN	ALAN TRAYNOR
		DATE	DATE	DATE
- 1		SEPTEMBER 2022	SEPTEMBER 2022	SEPTEMBER 2022

DRAWING No.

22-059A-101